Bruhath Benglauru Mahangara Palike, Dasarhalli Zone
Office of the Executive Engineer, Dasarhalli Division,
Schedule - B

Name of the Work : Improvements to roads and drains at abbigere old village near Govt., school abbigere in ward no. 12 Shettyhalli, shettyhalli sub division

Sl No	Item Name	Unit	Estimate Quantity	Rate to be Quoted for Unit Quantity in Words (Rs)	
				In Figures (Rs)	In Words (Rs)
1	Earthwork excavation by manual means in ordinary soil involving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specifications.	Cum	991.20	175.00	Rupees one Hundred and Seventy Five Only
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	92.70	5150.00	Rupees Five Thousand and One Hundred and Fifty Only
3	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with with 20mm and down size graded granite metal, coarse aggregate @ 0.69 cum and fine aggregates @ .460cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafairmed - 2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings,pedastals,retaining walls, staircase, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.	Cum	260.22	6360.00	Rupees Six Thousand and Three Hundred and Sixty Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner

Sl No	Item Name	Unit	Estimate Quantity	Rate to be Quoted by Sri. MR. Aswath Nara...	
				In Figures (Rs)	In Words
4	Providing and removing centering, shuttering, strutting.. propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached1 pilasters, buttresses, plinth cilis and string courses cost of all materials, labour complete as per specifications.	sqm	1739.70	308.50	Rupees ... Hundred ... Eight and ... Paisa ...
5	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Tonnes	15.80	64175.00	Rupees Six... Four Thousand and One Hundred Seventy Five Only
6	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specfications.	Sqm	562.50	1680.00	Rupees One Thousand Six Hundred and Eighty Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division

Scanned by CamScanner